

### MOM/OSHD/2023-06

Date: 8 September 2023

To: All Photovoltaic (PV) System Contractors, Installers and Other Interested Persons

### Circular on Safe Installation of Photovoltaic (PV) System

On 12 June 2023, a worker was electrocuted after coming into contact with the exposed cable of photovoltaic panel (PV) (refer to Annex A). He was subsequently conveyed to the hospital where he passed away on the same day.

2. As the installation of PV panels (or commonly known as solar panels) gains acceptance and wide adoption by building owners, it is crucial that industry stakeholders involved in installation of PV panels carry it out safely. In particular, MOM would like to highlight the following key risks and control measures for industry's compliance.

## Working at Height

3. As most PV panels are installed on the roof of the building, workers are exposed to the risks of falling from heights. The risks extend to workers undertaking preparatory work such as cleaning and waterproofing prior to the installation of the PV panels. Thus safe work-atheight measures must include, but not limited to, the following:

- i) Establish and implement a Fall Prevention Plan (FPP) and a permit-to-work system before commencing any installation of PV system on the roof;
- ii) Ensure that the risk control measures as stated in the FPP and permit-to-work (e.g., the use of travel restraint or fall arrest systems) have been communicated to the workers involved and implemented onsite;
- iii) Ensure that the workers involved are adequately trained to be familiarised with the hazards associated with working at height, and that they adhere to the risk control measures as implemented (e.g., wearing of body harness, secured to proper anchorage at all times, etc) when working on the roof.

#### Installation of PV system

4. The PV panels installed in open spaces such as rooftops, generate electricity when exposed to sunlight, even before the connection of the PV modules is completed or commissioned. Workers involved in PV panel installations must be briefed on electrical safety requirements, which shall include but not limiting to the requirements stipulated within the Electricity Act, the Electricity (Electrical Installations) Regulations and the Singapore Standard 638 - Code of Practice for Electrical Installations. The installation of the PV system shall be undertaken, carried out and/or supervised by a Licensed Electrical Worker (LEW) of the appropriate class.

5. Safety measures for the installation of PV modules shall include, but not limited to, the following:

- Ensure that the installation of PV module is in accordance to the PV single line diagram that has been approved and endorsed by a LEW of the appropriate class and to conduct open circuit voltage (V oc) measurement immediately on newly installed PV arrays to ensure that the total voltage does not exceed 1000 V DC;
- ii) Ensure that no live parts or conductors are exposed. Any breakdown or damage to the insulation of the cables and connectors shall be reported to the LEW immediately.
- iii) Treat all conductors as live, unless advised by the LEW otherwise; and
- All persons carrying out the installation must be equipped with appropriate personal protective equipment (PPE), such as safety shoes, insulative rubber gloves (OSHA rating: at least class 0), etc.

# Risk Management

6. In addition to the above risks, before commencing any work, a risk assessment (RA) must be conducted to evaluate the safety and health risks posed to any person who may be affected by the installation of the PV system. The RA must include, but not limited to, the following work activities and factors:

- i) Safe access to and egress from the work area and working at height;
- ii) Assessment of the roof's structural integrity;
- iii) Installation of PV system;
- iv) Assessment of weather conditions;
- v) Emergency responses, etc.

7. All reasonably practicable steps must be taken to ensure that the necessary risk control measures and safe work procedures are implemented to minimise and control the risks arising from the installation of PV system and working at height, among other considerations.

8. Please refer to Annex B on the list of relevant information and resources.

TAN SHI HAO, SEBASTIAN DIRECTOR OCCUPATIONAL SAFETY AND HEALTH INSPECTORATE MINISTRY OF MANPOWER

#### Annex A



Share this WSH Bulletin



Connect with Us

 We regret that we are unable to reply to emails at this email address.

 For engries or feedback, please email us at <u>contract@wshc.sg.</u>

 Visit the WSH Council's <u>website</u> now for updates on WSH-related matters, information and events.

Annex B

# List of relevant information and resources

- 1. Singapore Standards SS 638 (Code of Practice for electrical installations)
- 2. SS 601 Photovoltaic (PV) systems
- 3. IEC 62548 Photovoltaic (PV) arrays Design requirements
- 4. IEC 60364 Requirements for special installations or locations Solar Photovoltaic (PV) power supply systems
- 5. <u>Handbook for Solar Photovoltaic (PV) Systems by Energy Market Authority</u> <u>and Building Construction Authority</u>
- 6. <u>Best Practices for Installing Solar Panels on Building Rooftops by Building</u> <u>Construction Authority, Energy Market Authority and Urban Redevelopment</u> <u>Authority</u>
- 7. <u>PV guides</u> from SP Group resource page.